

1. 3:00 P.M. Agenda

Documents:

[2020-05-27 Joint Special Public Works - Parks And Commons Agenda.pdf](#)

2. Public Works & Streets Meeting Materials

Documents:

[Driftwood Estimate 05-06-20.Pdf](#)

[Driftwood Lane Draft Set 05-14-20.Pdf](#)

[Driftwood Sht 6 DRAFT 05-06-20.Pdf](#)



**CITY OF YACHATS
SPECIAL JOINT MEETING
PUBLIC WORKS & STREETS COMMISSION
AND PARKS & COMMONS COMMISSION
To Be Held Via ZOOM Meeting**

Wednesday May 27, 2020 at 3:00pm

Join Zoom Meeting

<https://us02web.zoom.us/j/89911257029?pwd=TFBQbFI1MDIRdFpHOXorbEZGWk1pdz09>

Meeting ID: 899 1125 7029

Password: 788079

One tap mobile

+13462487799,,89911257029#,,1#,788079# US (Houston)

+16699006833,,89911257029#,,1#,788079# US (San Jose)

Dial by your location

+1 346 248 7799 US (Houston)

+1 669 900 6833 US (San Jose)

+1 253 215 8782 US (Tacoma)

+1 312 626 6799 US (Chicago)

+1 929 205 6099 US (New York)

+1 301 715 8592 US (Germantown)

Meeting ID: 899 1125 7029

Password: 788079

Find your local number: <https://us02web.zoom.us/j/89911257029?pwd=TFBQbFI1MDIRdFpHOXorbEZGWk1pdz09>

SPECIAL JOINT MEETING AGENDA

- I. Current Business
 - A. Discussion of Driftwood Project.
 - B. VOTE of Driftwood Project

Adjourn meeting

This meeting is open to the public and all interested persons are invited to attend. This meeting will be audio taped. All items to be considered by the Commission must be submitted to City Hall no later than one week prior to the meeting. Minutes of all public meetings are available for review at City Hall, or on the City website at www.yachatsoregon.org.

In accordance with ORS 192.630, City of Yachats will make a good faith effort to provide accommodations for any person desiring to attend a public meeting, if the request is made at least 48 hours in advance of the meeting time. The meeting room is physically accessible to persons with mobility devices; a sign language or foreign language interpreter may be available, with advance notice. Call City Hall at 541- 547-3565 or Oregon Relay 1-800-735-2900 (TDD) two days in advance.

Posted 05-22-20





City of Yachats, Oregon
 Driftwood Lane
 3096.2021.0
 May 6, 2020

Engineer's Estimate

Item No.	Description	Estimated Quantity	Unit	Unit Price	Total Price
General Construction					
1.	Mobilization, Bonds, Permits and Insurance	All	L. S.	Lump Sum	\$10,000.00
2.	Erosion Control	All	L. S.	Lump Sum	\$2,000.00
3.	Traffic Control	All	L. S.	Lump Sum	\$2,000.00
4.	Surveying	All	L. S.	Lump Sum	\$2,500.00
5.	Testing and Quality Control	All	L. S.	Lump Sum	\$3,000.00
Subtotal - West 1st Street General					\$19,500.00
Street and Storm Drainage					
1.	Clearing, Grubbing & Demolition	All	L. S.	Lump Sum	\$6,000.00
2.	Sawcutting	120	L.F.	\$5.00	\$600.00
3.	Earthwork, Complete	All	L. S.	Lump Sum	\$15,000.00
4.	Overexcavation/Subgrade Stabilization Including Excavation, Reinforcement Geotextile Fabric, 1"-0" Crushed Rock Backfill	50	Cu.Yd.	\$75.00	\$3,750.00
5.	1"-0" Crushed Rock Base	650	Tons	\$30.00	\$19,500.00
6.	Type C Curb	520	L.F.	\$35.00	\$18,200.00
7.	P.C.C. Sidewalk, 4" Thick	2,200	S.F.	\$6.00	\$13,200.00
8.	ADA Ramps	7	Each	\$2,000.00	\$14,000.00
9.	CL C AC Pavement	240	Tons	\$160.00	\$38,400.00
10.	Connect to Existing Storm Drain	All	L. S.	Lump Sum	\$1,500.00
11.	8" CL 50 DI Storm Drain, Including Trench Excavation & Crushed Rock Backfill	26	L.F.	\$80.00	\$2,080.00
12.	Parking Lot Style Catch Basin	1	Each	\$2,000.00	\$3,000.00
13.	Signing and Striping	All	L. S.	Lump Sum	\$3,000.00
Subtotal - Street and Storm Drainage					\$138,230.00
Grand Total					\$157,730.00

FOR:
The City of Yachats, Oregon
P.O. Box 345
Yachats, Oregon 97498
(541) 547-3565


ABBREVIATIONS			
A.C. or ASPH.	ASPHALTIC CONCRETE	IRR.	IRRIGATION
A.D.	AREA DRAIN	INV.	INVERT
ASSEMBLY		J.B.	JUNCTION BOX
BLDG. or BLD.	BUILDING	L.P.	LIGHT POLE
BW	BOTTOM OF WALL	M	METER, MAIN
CATV	CABLE TELEVISION	M.B.	MAILBOX
C.B.	CATCH BASIN	M.H.	MANHOLE
C.O.	CLEAN-OUT	O.H.	OVER-HEAD
CONC.	CONCRETE	P/L or R	PROPERTY LINE
C. or C	CENTERLINE	P.P.	POWER POLE
D.	DUCTILE IRON	PVC	POLYVINYL CHLORIDE
E.C.	EDGE OF GRAVEL	PWR or P	POWER
E.O.P. or E.P.	EDGE OF PAVEMENT	R. or RAD.	RADIUS
ELEV.	ELEVATION	R.O.W. or R/W	RIGHT-OF-WAY
EX. or EXIST	EXISTING	SN, SEWER or S.S.	SANITARY SEWER
F.C.	FIN. DEPT. CONNECTOR	STD. or S.D.	STD. DRAIN
FT.	FEET	SVC.	SERVICE
F.F.	FINISH FLOOR	S/W	SIDEWALK
F.G.	FINISH GRADE	T.C.	TOP OF CURB
FI.H.	FIREFIGHTER	T. or T	TELEPHONE
F.I.	FIELD INLET	TRANS.	TRANSFORMER
F.M.	FORCE MAIN	TRAF. SIG. or T.S.	TRAFFIC SIGNAL
GRAV.	GRAVEL	TW	TOP OF WALL
G.M.	GAS METER	TYP.	TYPICAL
G.P.	GATE POST	U.C. or U/G	UNDER GROUND
G.S.	GROUND SHOT	UTIL.	UTILITY
G.S. VALVE	GAS VALVE	W/	WITH
H.	HANDICAP	WAT. or W	WATER
H.V.D.	HYDRAULIC	WLM.	WETLANDS MARKER
I.R.	IRON ROD	W.M.	WATER METER
I.P.	IRON PIPE	Y.P.C.	YELLOW PLASTIC CAP



Know what's below.
Call before you dig.



LOCATION MAP



VICINITY MAP

[illegible][illegible]

WE
WESTECH ENGINEERING, INC.
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97301
Phone: (503) 585-2474 Fax: (503) 585-3986
E-mail: westech@westech-eng.com

City of Yachats, Oregon
Driftwood Lane Street Improvements
Cover Sheet
Vicinity Maps &
Drawing Index

DRAWING


1

JOB NUMBER

3096.2021.0


5/14/2020 7:50:18 AM
R: \\Dwg\\Yachats\\2020 Driftwood St\\plot\\02 Notes.dwg, (Plot tab)

5/14/2020 7:50:43 AM
R:\Dwg\Yachats\2020 Driftwood St\plot\03 EC.dwg, (Layout1 tab)



EROSION CONTROL LEGEND:


- | | | |
|-----|---|------------------------------|
| (A) | ☐ | CATCH BASIN/INLET PROTECTION |
| (G) | ⊠ | CONCRETE TRUCK WASH-OUT AREA |



0 5 10 20
(Feet)

NO.	DATE	DESCRIPTION	BY
1			

VERIFY SCALE THIS IS ONE INCH ON ORIGINAL DRAWING IF NOT ONE INCH ON THIS SCALE, SCALE ACCORDINGLY	1"
DSN.	RCE
DRN.	RCE
CKD.	RCE
DATE:	MAY 2020



WESTECH ENGINEERING, INC.
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302
Phone: (503) 585-2474 Fax: (503) 585-3986
E-mail: westech@westech-eng.com

City of Yachats, Oregon
Driftwood Lane Street Improvements
Erosion Control Plan




DRAWING
3
JOB NUMBER
3096.2021.0

EROSION CONTROL NOTES:

- Clearing and grading erosion control measures shall be in place prior to site disturbance. All other necessary erosion control measures shall be implemented prior to starting work on the portion/phase of the project to which the measures are related. Erosion control measures shall be maintained in such a manner as to ensure that sediment and sediment-laden water does not enter the drainage system, roadways, or violate applicable water quality standards.
- The erosion control construction, maintenance, replacement and upgrading of the erosion control facilities is the responsibility of the Contractor until all construction is completed and approved, and permanent erosion control (i.e. vegetation/landscaping) is established on all disturbed areas.
- All recommended erosion control procedures are dependent on construction methods, staging, site conditions, weather and scheduling. During the construction period, erosion control facilities shall be upgraded as necessary due to unexpected storm events and to ensure that sediment and sediment laden water does not leave the site.
- The Contractor is responsible for control of sediment transport within project limits. If an installed erosion control system does not adequately contain sediment on site, then the erosion control measures shall be adjusted or supplemented by the Contractor as necessary to ensure that sediment laden water does not leave the site. Additional measures shall be provided as required to ensure that all paved areas are kept clean for the duration of the project. Additional interim measures will include, at a minimum, installation of sediment barriers or silt fences in accordance with the details shown on the drawings. These measures shall be installed along all exposed embankments and cut slopes to prevent sediment transport.
- All existing and newly constructed storm inlets and drains shall be protected until pavement surfaces are completed and/or vegetation is established.
- Erosion control facilities and sediment fences on active sites shall be inspected by the Contractor at least daily during any period with measurable precipitation. Any required repairs or maintenance shall be completed immediately. The erosion control facilities on inactive sites shall be inspected and maintained by the Contractor a minimum of once a month or within 24 hours following the start of a storm event.
- At no time shall sediment accumulation within a trapped catch basin exceed 50% of the sediment capacity. All catch basins and conveyance lines shall be cleaned prior to paving. The cleaning operation shall not flush sediment-laden water into the downstream system. The Contractor shall remove all accumulated sediment from all impacted catch basins and storm pipes prior to acceptance by the Owner.
- The Contractor is solely responsible for protection of all adjacent property and downstream facilities from erosion and siltation during project construction. Any damage resulting from such erosion and siltation shall be corrected at the sole expense of the Contractor.

- The Contractor shall provide site watering as necessary to prevent wind erosion of fine-grained soils.
- Unless otherwise indicated on the drawings, all temporary erosion control facilities, including sediment fences, silt sacks, bio-bags, etc. shall be removed by the Contractor within 30 days after permanent landscaping/vegetation is established.
- Sediment fences shall be constructed of continuous filter fabric to avoid use of joints. When joints are necessary, filter cloth shall be spliced together only at a support post, with a minimum 6-inch overlap, and both ends securely fastened to a post.
- Sediment fence shall be installed per drawing details. Sediment fences shall have adequate support to contain all silt and sediment captured.
- The standard strength filter fabric shall be fastened securely to stitched loops installed on the upslope side of the posts, and 6 inches of the fabric shall be extended into the trench. The fabric shall not extend more than 30 inches above the original ground surface. Filter fabric shall not be stapled to existing trees.
- Bio-filter bags shall be clean 100 percent wood product waste. Bags shall be 18-inch x 18-inch x 30-inch, weigh approximately 45 lbs., and be contained in a bag made of 1/2-inch plastic mesh.
- Sediment barriers shall be maintained until the up-slope area has been permanently stabilized. At no time shall more than 10-inches of sediment be allowed to accumulate behind sediment fences. No more than 2 inches of sediment shall be allowed to accumulate behind bio-filter bags. Sediment shall be removed prior to reaching the above stated depths. New sediment barriers shall be installed uphill as required to control sediment transport.
- Stabilized construction entrances shall be installed at the beginning of construction and maintained for the duration of the project. Additional measures may be required to ensure that all paved areas are kept clean for the duration of the project.
- The Contractor shall verify that all trucks are well sealed when transporting saturated soils from the site. Water drippage from trucks transporting saturated soils must be reduced to less than 1 gallon per hour prior to leaving the site.
- The entrance shall be maintained in a condition that will prevent tracking or flow of mud onto the public right-of-way or approved access point. The entrance may require periodic top dressing as conditions demand, and repair and/or clean out of any structures used to trap sediment.
- All materials spilled, dropped, washed, or tracked from vehicles onto roadways or into storm drains must be removed immediately, and the Contractor shall provide protection of downstream inlets and catch basins to ensure sediment laden water does not enter the storm drain system.

- Temporary grass cover measures must be fully established by Oct 15th, or other cover measures (ie. erosion control blankets with anchors, 3-inches minimum of straw mulch, 6 mil HDPE plastic sheet, etc.) shall be in place over all disturbed soil areas until April 30th. To establish an adequate grass stand for controlling erosion by Oct 15th, it is recommended that seeding and mulching occur by September 1st. Straw mulch, if used, shall not leave any bare ground visible through the straw.
- Minimum wet weather slope protection. For slopes steeper than 3H:1V but less than 2H:1V, use Tensor/North American Green Type S150 erosion control blanket. For slopes 2H:1V or steeper, use Tensor/North American Green Type SC150 erosion control blanket. Use a minimum of 2-inches straw mulch or Tensor/North American Green Type S150 for slopes flatter than 3H:1V. Slope protection shall be placed on all disturbed areas immediately after completion of each section of construction activity, until the erosion control seeding has been established. As an option during temporary or seasonal work stoppages, a 6-mil HDPE plastic sheet may be placed on exposed slopes. The plastic sheet shall be provided with an anchor trench at the top and bottom of the slope, and shall be sandbagged on the slopes as required to prevent damage or displacement by wind.
- Permanent erosion control vegetation on all embankments and disturbed areas shall be re-established as soon as construction is completed.
- Soil preparation. Topsoil should be prepared according to landscape plans, if available, or recommendations of grass seed supplier. It is recommended that slopes be textured before seeding by rack walking (ie. driving a crawling tractor up and down the slopes to leave a pattern of cleat imprints parallel to slope contours) or other method to provide stable areas for seeds to rest.
- When used, hydromulch shall be applied with grass seed at a rate of 2000 lbs. per acre between April 30 and June 10, or between September 1 and October 1. On slopes steeper than 10 percent, hydroseed and mulch shall be applied with a bonding agent (tackifier). Application rate and methodology to be in accordance with seed supplier recommendations.
- When used in lieu of hydromulch, dry, loose, weed free straw used as mulch shall be applied at a rate of 4000 lbs. per acre (double the hydromulch application requirement). Anchor straw by working in by hand or with equipment (rollers, cleat trackers, etc.). Mulch shall be spread uniformly immediately following seeding.
- When conditions are not favorable to germination and establishment of the grass seed, the Contractor shall irrigate the seeded and mulched areas as required to establish the grass cover.
- Seeding. Recommended erosion control grass seed mix is as follows. Dwarf grass mix (low height, low maintenance) consisting of dwarf perennial ryegrass (80% by weight), creeping red fescue (20% by weight). Application rate shall be 100 lbs. per acre minimum.
- Grass seed shall be fertilized at a rate of 10 lbs. per 1000 S.F with 16-16-16 slow release type fertilizer. Development areas within 50 feet of water bodies and wetlands must use a non-phosphorous fertilizer.



VERIFIED SCALE BAR IS ONE INCH ON ORIGINAL DRAWING IF NOT ONE INCH ON THIS SCALE, DIMENSIONS SHALL BE ACCORDINGLY ADJUSTED	DATE: MAY 2020	NO. 1	DESCRIPTION	BY
DSN: RCE	DRN: RCE	CKD: RCE		
REVISIONS				

REVIEW

PROFESSIONAL ENGINEER
STATE OF OREGON
EXPIRATION DATE: 12/31/2021

WESTECH ENGINEERING, INC.
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302
Phone: (503) 585-2474 Fax: (503) 585-3986
E-mail: westech@westech-eng.com

City of Yachats, Oregon


Driftwood Lane Street Improvements

Erosion Control
Notes & Details

DRAWING
4


JOB NUMBER
3096.2021.0

5/14/2020 7:51:33 AM
R:\Dwg\Yachats\2020 Driftwood St\Plot\05 Survey.dwg, (Plot tab)



- REMOVAL/RELOCATION LEGEND**
- (P) CONTRACTOR TO PROTECT FROM DAMAGE.
 - (R) REMOVE/RELOCATE BY OTHERS. CONTRACTOR TO COORDINATE.
 - (R1) CONTRACTOR TO REMOVE/DISPOSE OFF SITE.
 - (R2) CONTRACTOR TO RELOCATE.
 - (S) CONTRACTOR TO SAWCUT A.C. PAVEMENT OR CONCRETE.
 - (A) CONTRACTOR TO ABANDON IN PLACE.

NOTES:
THIS DEMOLITION PLAN IS PROVIDED AS A GUIDE TO ASSIST THE CONTRACTOR IN IDENTIFYING THE SCOPE OF WORK REQUIRED TO REMOVE EXISTING INFRASTRUCTURE AND MATERIALS PRIOR TO STARTING CONSTRUCTION. THE CONTRACTOR IS RESPONSIBLE FOR REVIEWING EXISTING CONDITIONS AND INFORMATION TO DETERMINE THE FULL SCOPE OF DEMOLITION WORK REQUIRED TO CONSTRUCT THE PROJECT CONSISTENT WITH THE PLANS AND SPECIFICATIONS.



0 5 10 20
(Feet)

NO.	DATE	DESCRIPTION	BY
1	NOV 15, 2019	REVISION	
2			
3			
4			
5			
6			
7			
8			
9			
10			

VERIFY SCALE
PLOT IS ONE INCH ON ORIGINAL DRAWING
IF NOT ONE INCH ON PLOT, SCALES ACCORDINGLY

1"

0

DSN. RCE
DRN. RCE
CKD. RCE

NO. 1
DATE MAY 2020

DATE: MAY 2020

WE **WESTECH ENGINEERING, INC.**
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302
Phone: (503) 585-2474 Fax: (503) 585-3986
E-mail: westech@westech-eng.com

City of Yachats, Oregon



Driftwood Lane Street Improvements

Driftwood Lane

Survey & Demolition Plan

DRAWING
5

JOB NUMBER
3096.2021.0

City of Yachats, Oregon

Driftwood Lane Site Plan

6

3096.2021.0

N

WESTECH ENGINEERING, INC.
CONSULTING ENGINEERS AND PLANNERS

1 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302
Phone: (503) 585-2474 Fax: (503) 585-3986
E-mail: westech@westech-eng.com



VERIFY SCALE
BAR IS ONE INCH ON
ORIGINAL DRAWING



IF NOT ONE INCH ON THIS SHEET, ADJUST SCALES ACCORDINGLY

DSN.	RCE
DRN.	RCE

CKD. RCE
DATE: MAY 2020

REVISIONS	DESCRIPTION
1	Initial version
2	Added new section on data collection
3	Revised methodology section
4	Added references to recent studies
5	Final version

5/14/2020 7:52:48 AM
R:\Dwg\Yachats\2020 Driftwood St\Plot\07 Grading.dwg, (Layout1 tab)



0 5 10 20
(Feet)

City of Yachats, Oregon

Driftwood Lane Street Improvements

Driftwood Lane
Grading Plan

DRAWING

7

JOB NUMBER

3096.2021.0



WESTECH ENGINEERING, INC.
CONSULTING ENGINEERS AND PLANNERS

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302
Phone: (503) 585-2474 Fax: (503) 585-3986
E-mail: westech@westech-eng.com









VERIFY SCALE
THIS IS ONE INCH ON
ORIGINAL DRAWING
IF NOT ONE INCH ON
THIS DRAWING, SCALE
APPROPRIATELY

0 1"


DSN. RCE
DRN. RCE
CKD. RCE

NO. 1
DATE MAY 2020
REVISIONS

BY



VERIFIED SCALE	1"
DATE: MAY 2020	
NO.	1
DATE	
DESCRIPTION	
REVISIONS	
BY	
DRN.	RCE
CKD.	RCE
DATE	MAY 2020




WESTTECH ENGINEERING, INC.
CONSULTING ENGINEERS AND PLANNERS

WE

3841 Fairview Industrial Dr. S.E., Suite 100, Salem, OR 97302
Phone: (503) 585-2474 Fax: (503) 585-3986
E-mail: westtech@westtech-eng.com

City of Yachats, Oregon
Driftwood Lane Street Improvements
**Driftwood Lane
Cross Sections**



Curve Table					
Curve #	Length	Radius	Delta	Chord Direction	Chord Length
C3	10.75'	5.00	123.16°	N66° 52' 24"E	8.79'
C4	7.36'	13.50	31.23°	S20° 54' 38"W	7.27'
C1	31.42'	20.00	90.00°	S50° 17' 39"W	28.28'
C2	20.87'	25.00	47.84°	S27° 37' 36"E	20.27'