

1. Agenda

Documents:

[2017-05-09 Public Works And Streets Agenda.pdf](#)

2. Meeting Materials

Documents:

[2017-04-18 South Tank DWS Conditional Approval.pdf](#)

[2017-05-09 Public Works Department Report.pdf](#)



CITY OF YACHATS

PUBLIC WORKS & STREETS COMMISSION MEETING

441 Hwy 101 N., Yachats Commons, Room 1

Tuesday, May 9, 2017 at 3:00pm

AGENDA

- I. Introduction of new chair, John Moore
- II. Meeting called to order
- II. Minutes of April 11, 2017
- III. Reports
 - A. South Tank Project
 - B. Public Works Department
 - D. Solid Waste District Advisory Council
- Business
 - A. Clean Sweep
- V. Other Business
 - A. From the Commission
 - B. From the Staff
 - C. From the Floor

This meeting is open to the public and all interested persons are invited to attend. This meeting will be audio taped. All items to be considered by the Commission must be submitted to City Hall no later than one week prior to the meeting. Minutes of all public meetings are available for review at City Hall, or on the City website at www.yachatsoregon.org.

In accordance with ORS 192.630, City of Yachats will make a good faith effort to provide accommodations for any person desiring to attend a public meeting, if the request is made at least 48 hours in advance of the meeting time. The meeting room is physically accessible to persons with mobility devices; a sign language or foreign language interpreter may be available, with advance notice. Call City Hall at 541- 547-3565 or Oregon Relay 1-800-735-2900 (TDD) two days in advance.

Posted: 05-03-17





April 18, 2017

Rick McClung
City of Yachats
P.O. Box 345
Yachats, OR 97498

Re: **South Tank Water System Improvements (PR#2017-27)**
City of Yachats (PWS#00966)
Conditional Approval

Dear Rick McClung:

Thank you for your submittal of plan review information for the South Tank Water System Improvements for the City of Yachats to the Oregon Health Authority's Drinking Water Services (DWS). On March 15, 2017, our office received construction plans. The plan review fee of \$3300 was also received. At this time DWS grants conditional approval.

The project includes construction of a 0.25 MG glass-fused-to-steel storage tank with an interior mixing system and approximately 1,400 feet of 8" PVC waterline. The project also includes 24" storm sewer but is not covered in this plan review. The storage tank will be constructed on Crestview Drive, off of Hwy 101.

The plans are approved with the following condition:

- Provide bacteria results showing the new water storage tank and water lines are free of coliform bacteria.

Until we receive verification that the project was completed with the conditions listed above met and we have granted Final Approval for the project, the waterlines and storage tank are not approved for use.

Upon completion of the project, please verify in writing that construction was completed according to the submitted plans and conditions listed above. If substantial changes are made, a set of record (as-built) drawings must be submitted. Documentation

Page 2 of 2


City of Yachats (PWS# 00966) South Tank Water System Improvements
PR No. 2017-27 - Conditional Approval
April 18, 2017

demonstrating how the above conditions were met should reference Plan Review #2017-27 and can be e-mailed to me at rebecca.a.templin@state.or.us or mailed to:

Attn: Rebecca Templin
OHA-Oregon Drinking Water Services
444 A Street
Springfield, OR 97477

If you have any questions or would like this in an alternate format, please feel free to call me at (541) 726-2587 x29.

Sincerely,



Rebecca Templin, P.E.
Regional Engineer
Drinking Water Services

cc: Julie Wray, DWS Portland
Tia Skerbeck, DWS Portland
Matt Wadlington, P.E., Civil West Engineering Services, Inc.



City of Yachats
PUBLIC WORKS DEPARTMENT
500 W. 7th St.
P.O. Box 345
Yachats, OR 97498

Date: May 1, 2017
To: Joan Davies City Manager
From: Public Works
Re: April 2017 Public Works Report

Total Rain fall for the month of April 2017:	7.77 inches
Wastewater treated for the month of April 2017:	6,529,000 gallons
Water production for the month of April 2017:	3,341,300 gallons

Streets:

- Contracted with tree removal company to remove trees on Mitchell Lane and W. 2nd Street.
- Assembled and placed street signs for Diversity Lane, Hill Court and the Post Office.

Water:

- Built intake pipe for Reedy Creek headworks.
- Multiple screen clean outs at the Reedy Creek meter house.
- Prepared for and had a water plant inspection from Oregon Health Authority.

Distribution Sys:

- Installed water service at 87 Crestview.
 - Installed temporary water service at the Dollar General.
 - Cleaned Raw Reservoir (14 man hours).
 - Repaired broken water line on 4th street.
 - Meters read and then read meter rereads.
 - Prepared for and had a water reservoir inspection from Oregon Health Authority.
 - Cleaned roof tops of the million gallon and 250k reservoirs.
 - Cleaned gutters on million gallon reservoir.
 - Relocated water line at Toppers.
-

Sewer:

- Hauled one 10-yard load of biosolids to Heard Farms (open again).
- Sewer plant maintenance.
- Repaired biosolids pump.
- Processed second load of biosolids to haul to Heard Farms.
- Contract service on all Generators.

Sewer CIP:

- SCADA System installed, reporting package is almost done but ready for DEQ electronic filing.
- Library trail has been moved. Fence post are being set.

Collection Sys:

- CCTV'd 250 feet of collection pipe.
- Sent a private sewer lateral repair notice.
- Relocated sewer lateral at Toppers.
- Power failure from service line to the Main pump station. No issues, operated on generator.

Storm Drainage:

- Located and exposed a culvert at the end of West 6th next to the Public Works fence.

Parks & Commons:

- Picked up brush piles on 4th Street and at the ball field.
- Removed "Hanging" back stop section from ball field.
- Cut and removed two large tree limbs in front of the Commons.